

Alpilla Enerji Üretim A.Ş.

Alpilla 600 MW Combined Cycle Power Plant

Site, Existing Infrastructure and Tie-in Points

Document number	ALP-OWN-GEN-001
Revision	1
Date	2026-09-27
Status	Issued for contract (Rev 1: drawings added, temporary area defined, TQ answers incorporated)
Confidentiality	Restricted - Contract ALP-EPC-001 parties only

	Prepared	Checked	Approved
Function	Owner's Engineer (discipline lead)	Owner's Engineer (project engineer)	Owner's Project Director
Signature / date	signed 2026-09-27	signed 2026-09-27	signed 2026-09-27

Rev	Date	Description
0	2026-09-14	Issued for tender / contract
1	2026-09-27	Issued for contract (Rev 1: drawings added, temporary area defined, TQ answers incorporated)

CASE STUDY - all organisations, data and signatures are fictional.

1. Site

- Plot area 12.0 ha: rectangle 400 m (east–west) × 300 m (north–south), plant grid origin (E 0, N 0) at the south-west corner, plant north = true north. Grid coordinates in metres; geographic coordinates will be given in the land survey (UTM 35N).
- Shoreline 60 m south of the southern plot boundary; the 60 m strip is public coastal land (no permanent structures except intake/outfall pipes and a temporary landing structure under separate permit).
- Levelled by the Owner to +15.0 m (completed 2025); compaction records available.
- A seasonal stream runs in a concrete channel (3 m × 2 m) along the western boundary (E 0–10 m), discharging to the sea. A 10 m maintenance/flood buffer from the channel is required by the water authority.
- Usable area** after the coastal setback, the channel buffer and a 5 m boundary landscaping strip: about 10.6 ha.
- Temporary construction area (TP-A1): 5.04 ha field immediately north of the plot and west of the access road, E 0–180, N 320–600 (180 m × 280 m), leased by the Owner and available free of charge from 2027-03-01 until Taking-Over (TQ-012). The field is at +14.0 to +15.5 m, grassland, no services; the Contractor levels, fences and restores it.
- Drawings: **ALP-OWN-DWG-001** (external connections) and **ALP-OWN-DWG-002** (site and construction area plan) form part of this document.

2. Existing features on the Site

Feature	Location (plant grid)	Status / responsibility
Buried 11 kV distribution cable of the regional utility	along the east boundary, E 390, N 0–300, depth 1.0 m	Owner to have it relocated outside the plot by 2027-06-30
Abandoned concrete foundations of a former warehouse (about 1,200 m ²)	E 300–360, N 20–60	Contractor to demolish and remove (debris non-hazardous per Owner survey)
Owner's meteorological mast	E 20, N 280	to be kept until Taking-Over; relocate at Contractor's cost if in conflict
Groundwater observation wells (3)	per survey	keep or replace

3. Access and heavy transport

- Existing asphalt access road (6 m wide) from the state road (1.2 km north) to the north gate at E 200, N 300.
- State road has **two bridges limited to 120 t gross vehicle weight**. Components heavier than about 90 t (GT, generators, GSU transformers, HRS modules above 90 t) cannot use the road.
- Nearest port with heavy-lift quay (400 t crane) and RoRo ramp: 18 km by sea, 26 km by road.
- No jetty or barge landing exists at the Site.** A temporary barge landing on the coastal strip is permissible under a separate coastal permit, which the Owner can apply for once the Contractor provides the design (permit duration about 6 months).

4. Utilities and tie-in points available at the plot boundary

Tie-in	Description	Location (plant grid)	Owner provides	Available by
TP-G1	Natural gas: 16" spur line from the transmission system with tap valve station (4.5 km)	E 380, N 300 (north-east corner), EL +14.0 flange	pipeline, isolation valve, insulating joint	2028-06-30
TP-E1	380 kV double-circuit overhead line from the TSO substation (7 km)	line gantry E 30, N 290	line up to and including the dead-end tower; conductors to the gantry	2028-07-15 (TQ-010)
TP-E2	Construction power 34.5 kV, 5 MVA, from distribution network	north gate	connection agreement, meter	2027-02-28
TP-W1	Potable water DN150 municipal main, 3 barg, 20 m ³ /h	north gate	connection and meter	2027-02-28

Tie-in	Description	Location (plant grid)	Owner provides	Available by
TP-S1	Sanitary wastewater	—	no municipal sewer available; Contractor's packaged treatment plant discharges via the outfall (TQ-008)	—
TP-T1	Telecommunication fibre (2 operators)	north gate	ducts to the plot boundary	2027-06-30
TP-R1	Access road	north gate E 200, N 300	existing road, maintained by Owner	available
TP-CW1	Seawater intake head	about 650 m offshore, –12 m	seabed survey, marine permit	permit by 2027-04-30
TP-CW2	Outfall diffuser	about 350 m offshore, ≥ 250 m from intake	marine permit	permit by 2027-04-30
TP-D1	Storm water discharge	to the western stream channel (max 2 m ³ /s) or to sea	water authority consent	available
TP-L1	LDO supply by road tankers	north gate	supply contract, first fill	first fill by first fire
TP-M1	Temporary barge landing	public coastal strip, around E 120, N –40	coastal permit (application by 2027-04-30)	2027-09-30 (target)
TP-A1	Temporary construction area 5.04 ha	E 0–180, N 320–600	lease, free of charge	2027-03-01

5. Routes of the external connections (see ALP-OWN-DWG-001)

Connection	Route	Length
Access road	from the state road (junction at about E 200, N 1,500) south to the north gate	1.2 km
Gas spur line 16"	from the tap valve station on the transmission line (about E 900, N 4,800) south, crossing the state road, to TP-G1	4.5 km
380 kV OHL	from TSO substation "Kıyı" (about E –4,500, N 5,600) south-east to the line gantry TP-E1	7.0 km
Potable water DN150, 34.5 kV line, fibre	along the access road from the state road to the north gate	1.2 km
Heavy transport	by sea from the heavy-lift port (18 km) to the barge landing TP-M1	18 km

6. Neighbours and constraints

- Nearest residential receptor: village houses 900 m north-east of the plot centre.
- Industrial neighbour (cement terminal) 700 m west.
- Height restriction from the civil aviation authority: 120 m above grade within the plot (no conflict expected with a 60–70 m stack).