

IMAGINARY ELECTRIC COMPANY

Power Generation Division - Plant Integration

Alpilla 600 MW Combined Cycle Power Plant - 1 x IE-9H.02 multi-shaft power island

Power Island Thermal Performance Data (Heat Balance)

Document number	IEC-ALP-PER-001
Revision	B
Date	2026-09-28
Status	Revised for EPC engineering - supersedes Rev 0
Addressee	Istanbul EPC Muhendislik ve Taahhut A.S. (consortium leader) - EPC engineering
Contract	ALP-EPC-001 (Owner contract); consortium agreement IEPC-IEC

	Prepared	Checked	Approved
Function	IEC plant integration engineer	IEC lead engineer (discipline)	IEC project engineering manager
Signature / date	signed 2026-09-28	signed 2026-09-28	signed 2026-09-28

Rev	Date	Description
0	2026-09-27	Issued for EPC engineering (reference data)
A	2026-09-27	EPC piping values (TQ-IEC-003/012), revised guarantees (TQ-IEC-001/005/009), IG-07 (TQ-IEC-013)
B	2026-09-28	HRSG arrangement corrected: IP SH and LP SH positions, LP steam 250 degC (TQ-IEC-016)

CASE STUDY - Imaginary Electric, its products and all data are fictional.

1. Purpose and basis

This document gives the expected thermal performance of the IEC power island (1 x IE-9H.02 gas turbine with generator, 1 x IE-HR3 triple-pressure reheat HRSG, 1 x IE-ST3R reheat steam turbine with generator, seawater condenser) for the EPC's plant heat and mass balance. Values are **expected values, new and clean**, without guarantee margins; IEC's guarantee values to the consortium are given in section 7.

- Case **SRC-NG-100**: Site Reference Conditions per ER-02.03 - ambient 15.0 degC, 70 % RH, 1011.5 mbar; seawater 16.0 degC; base load on natural gas; power factor 0.85 lagging; 50.0 Hz.
- Fuel: Owner reference composition ALP-OWN-FUL-001 / ER-03.02. **LHV calculated per ISO 6976 from this composition: 47.48 MJ/kg (34.78 MJ/Sm3, 15 degC/15 degC)**. Heat input = fuel mass flow x this LHV. Fuel gas heated to 215 degC in the IEC performance gas heater with IP feedwater.
- GT inlet pressure loss 10 mbar, exhaust back-pressure 36 mbar (HRSG 30 mbar + stack 6 mbar, stack by EPC).
- Steam piping between HRSG and steam turbine is **by EPC. Rev A: pressure and temperature drops per the EPC preliminary piping design (TQ-IEC-003)**: HP 5.5 bar / 1.5 K, hot reheat 1.4 bar / 1.5 K, cold reheat 0.7 bar / 1 K, LP 0.35 bar / 1 K. Correction: +1 bar HP piping pressure drop = -0.10 MW ST output.
- Boiler feed pumps and condensate pumps are by EPC; IEC assumed BFP discharge 209 bar(a) (HP) / 46 bar(a) (IP), CEP discharge 16 bar(a).
- Steam turbine gland leak-offs, valve stem leakages and HRSG blowdown are not shown in this summary heat balance (blowdown zero at design; leak-offs are internal to the ST).

2. Summary at SRC-NG-100

Item	Value	Unit
GT output at generator terminals	425.00	MW
GT heat rate (LHV)	8,314.1	kJ/kWh
GT heat input (LHV)	981.52	MW
Fuel gas flow	20.672 kg/s = 101,596	Sm3/h
Compressor inlet air flow	776.01	kg/s
GT exhaust flow / temperature	796.68 / 640.0	kg/s / degC
GT generator efficiency	98.90	%
GT losses other than generator (lube oil, radiation)	3.80	MW
Performance gas heater duty	9.46	MW
HRSG heat transferred to water/steam	501.10	MW
HRSG heat loss (casing, % of gas-side duty)	0.4	%
Stack temperature	80.2	degC
ST output at generator terminals	200.73	MW
ST mechanical / generator efficiency	99.55 / 98.80	%
Condenser pressure	34.44	mbar(a)
Condenser duty	290.46	MW
Circulating water flow (7 K rise)	10,197 kg/s = 36,113	m3/h
Power island gross output	625.73	MW
Power island gross heat rate (LHV)	5,647.0	kJ/kWh

Net output and net heat rate depend on the EPC balance-of-plant auxiliary loads and transformer losses; IEC's auxiliary loads are listed in IEC-ALP-REQ-001 section 7.

3. Stream data at SRC-NG-100

Node codes: AMB ambient, FGS EPC fuel gas system, FGH IEC performance gas heater, GT gas turbine, HRSG, STK stack (EPC), PIPE steam piping HRSG-ST (EPC), ST steam turbine, COND condenser, CEP condensate pumps (EPC), CMIX condensate/FGH-return junction (EPC), BFP boiler feed pumps (EPC), SEA intake, OUT outfall.

No	Description	Fluid	From	To	Flow kg/s	p bar(a)	T degC	h kJ/kg
1	Ambient air to GT compressor inlet	air	AMB	GT	776.01	1.01	15.0	-
2	Fuel gas at performance gas heater inlet (IEC terminal point)	fuel_gas	FGS	FGH	20.67	38.00	25.0	-
3	Heated fuel gas to GT combustion system	fuel_gas	FGH	GT	20.67	35.50	215.0	-
4	GT exhaust gas to HRSG inlet	flue_gas	GT	HRSG	796.68	1.05	640.0	-
5	Flue gas at HRSG outlet to stack	flue_gas	HRSG	STK	796.68	1.01	80.2	-
6	HP steam at HRSG outlet (HP SH outlet)	steam	HRSG	PIPE	100.15	187.00	600.0	-
7	HP steam at ST main stop valve inlet	steam	PIPE	ST	100.15	181.50	598.5	-
8	Cold reheat steam at HP turbine exhaust	steam	ST	PIPE	100.15	40.20	366.2	-
9	Cold reheat steam at HRSG reheater inlet	steam	PIPE	HRSG	100.15	39.50	365.2	-
10	IP superheated steam (joins cold reheat inside the HRSG)	steam	HRSG	HRSG	17.34	40.30	330.0	-
11	Hot reheat steam at HRSG outlet	steam	HRSG	PIPE	117.49	37.60	600.0	-
12	Hot reheat steam at ST IP stop/control valve inlet	steam	PIPE	ST	117.49	36.20	598.5	-
13	LP steam at HRSG outlet	steam	HRSG	PIPE	11.90	5.40	250.0	-
14	LP steam at ST LP admission	steam	PIPE	ST	11.90	5.05	249.0	-
15	IP turbine exhaust (crossover, internal)	steam	ST	ST	117.49	4.95	309.2	-
16	LP turbine exhaust to condenser (UEEP)	steam	ST	COND	129.39	0.0344	26.4	2,355.5
17	Condensate at hotwell outlet / CEP suction	water	COND	CEP	129.39	0.0344	26.3	-
18	Condensate at CEP discharge	water	CEP	CMIX	129.39	16.00	26.5	-
19	Fuel gas heater water return to condensate	water	FGH	CMIX	12.48	43.00	75.0	-
20	Condensate to HRSG condensate preheater inlet	water	CMIX	HRSG	141.87	15.50	30.8	-
21	Feedwater from LP drum to boiler feed pumps	water	HRSG	BFP	129.97	5.90	158.1	-
22	HP feedwater at BFP discharge	water	BFP	HRSG	100.15	209.00	161.8	-
23	IP feedwater at BFP interstage outlet	water	BFP	HRSG	29.82	46.00	158.9	-
24	IP economiser water to performance fuel gas heater	water	HRSG	FGH	12.48	43.30	248.0	-
25	Circulating seawater to condenser inlet	seawater	SEA	COND	10,196.80	2.50	16.0	-
26	Circulating seawater from condenser outlet	seawater	COND	OUT	10,196.80	1.70	23.0	-

4. GT exhaust gas composition at SRC-NG-100 (mol %, wet)

N2	O2	Ar	CO2	H2O
73.85	11.12	0.88	4.47	9.67

5. HRSG temperature profile at SRC-NG-100

HRSG section (gas flow order)	Gas in degC	Gas out degC	Duty MW
HPSH / RH	640.0	450.6	176.83
HPEVAP	450.6	371.6	71.38
IPSH	371.6	366.9	4.19
HPECO2	366.9	295.1	63.71
IPEVAP	295.1	261.0	29.89

HRSG section (gas flow order)	Gas in degC	Gas out degC	Duty MW
LPSH	261.0	258.2	2.43
HPECO1 / IPECO	258.2	198.7	51.64
LPEVAP	198.7	166.2	27.91
CPH	166.2	80.2	73.12

Pinch points HP/IP/LP: 8 / 8 / 8 K; approach temperatures at the economiser outlets: 5 / 5 / 5 K. Drum saturation temperatures HP/IP/LP: 363.6 / 253.0 / 158.2 degC. Steam turbine section outputs (shaft): HP 41.94 MW, IP 69.40 MW, LP 92.74 MW; LP exhaust moisture 7.94 %.

Rev B (TQ-IEC-016): the HRSG arrangement of Rev 0/Rev A placed the IP superheater after HP economiser 2 and the LP superheater after HP economiser 1 / IP economiser, where the gas is colder than the steam outlet (temperature cross). Corrected arrangement: IP superheater directly after the HP evaporator, LP superheater directly after the IP evaporator; LP steam temperature 250 degC. Rated off-design heat balances: IEC-ALP-PER-003.

6. Performance at other ambient conditions and part load (estimates)

Base load on natural gas, seawater temperature as shown, other conditions as SRC. GT from the IE-9H.02 correction curves; the bottoming cycle is re-estimated with the design pinch/approach values. **These are preliminary estimates, not off-design ratings of the fixed HRSG and condenser surfaces;** rated off-design heat balances follow with the HRSG thermal design (IEC-ALP-DS-104 Rev A).

Ambient degC	RH %	Seawater degC	GT MW	GT HR kJ/kWh	Exhaust kg/s	Exhaust degC	ST MW	Gross MW	Gross HR kJ/kWh	Condenser mbar	Gas Sm ³ /h	Remark
-8.0	80	6.9	470.0	8,089	823.5	634.0	211.1	681.1	5,582	19.8	109,310	GT at output limit 470 MW
-4.8	80	8.0	470.0	8,131	832.5	635.7	213.4	683.4	5,592	21.2	109,874	GT at output limit 470 MW
5.0	75	11.0	452.8	8,217	829.2	634.8	209.7	662.5	5,616	25.5	106,984	
15.0	70	16.0	425.0	8,314	796.7	640.0	200.7	625.7	5,647	34.4	101,596	
25.0	55	22.0	397.2	8,411	761.8	645.2	190.4	587.6	5,685	48.7	96,053	
32.8	45	24.0	372.8	8,501	729.5	649.3	183.3	556.1	5,699	54.4	91,121	
40.0	35	27.0	348.2	8,595	695.9	653.0	174.7	522.9	5,724	64.2	86,055	

GT output is limited to **470 MW** at the generator terminals (generator and shaft limit) below about -1 degC; the GT then runs at part load with the IGV closing.

GT load %	GT MW	GT HR kJ/kWh	Exhaust kg/s	Exhaust degC	ST MW	Gross MW	Gross HR kJ/kWh
100	425.0	8,314	796.7	640.0	200.7	625.7	5,647
80	340.0	8,746	696.5	640.0	175.2	515.2	5,772
60	255.0	9,436	593.1	640.0	148.8	403.8	5,959
50	212.5	9,894	541.0	632.0	132.6	345.1	6,092
40	170.0	10,600	496.9	615.0	115.9	285.9	6,303

Part load at SRC with the steam cycle at fixed pressure (sliding-pressure operation will be optimised in detailed design; values are conservative estimates).

7. IEC guarantees to the consortium (power island)

Guarantee (SRC-NG-100, new and clean, per ASME PTC 46 / ISO 2314)	Value
Power island gross output at generator terminals	not less than 615.0 MW (TQ-IEC-001)
Power island gross heat rate (LHV)	not more than 5,735 kJ/kWh (TQ-IEC-001)
GT output at generator terminals	not less than 418.0 MW
Condenser pressure at 16.0 degC seawater, 36,050-38,000 m ³ /h corrected to 36,050 m ³ /h, ball cleaning in operation (TQ-IEC-005/009)	not more than 35.5 mbar(a)
IEC auxiliary loads (IEC-ALP-REQ-001 table 7.1, excl. GSU losses)	not more than 2,700 kW
NO _x / CO at HRSG outlet (15 % O ₂ , dry), 40-100 % GT load, natural gas	30 / 30 mg/Nm ³
Power island gross heat rate at the GT load for 60 % plant net load (TQ-IEC-013)	not more than 6,060 kJ/kWh

Degradation is excluded from the values above; recoverable and non-recoverable degradation curves follow in IEC-ALP-PER-002.