



PLAN (grid E/N m)



ELEVATION ON GT AXIS (looking north), EL m



1. WEIGHTS AND LIFTS

Item	t	L x W x H m	Remark
GT core engine (shipping)	405	13.2 x 5.9 x 5.6	DS-101; SPMT via west door, skidded
GT rotor (maintenance lift)	112	11.0 x 3.2 x 3.2	120 t hook, lifting beam by IEC
Compressor / turbine casing upper halves	≤ 48	per IEC manual	laid on stands in the laydown
Exhaust diffuser (2 pieces)	2 x 62	8.5 x 7.2 x 7.0	hall crane
Generator stator	340	10.8 x 4.6 x 4.9	DS-102; jacking and skidding, no crane lift
Generator rotor	72	about 12.5 long	withdrawn west with IEC rotor carriage, 15 m clear
Filter house modules	≤ 28	18 modules	25 t mobile crane from the south access strip

2. MAINTENANCE AND INSTALLATION REQUIREMENTS

Requirement	IEC requirement (EPC to provide)
Crane	EOT 120 t main / 20 t auxiliary; hook max ≥ EL +32.0 (17 m above grade); hook covers GT, generator, diffuser and the laydown.
Laydown	900 m2 at 10 t/m2 inside the hall next to the GT (major inspection every 50,000 EOH, 35 days).
Access doors	west door 8 m wide x 9 m high on the GT axis for SPMT (GT core 405 t, stator 340 t); personnel doors at both ends of the hall.
Clearances	1.2 m walkway around the enclosure; 3.0 m in front of enclosure doors and the lube oil skid; filter house access strip 6 m on the south side.
Foundations	GT and generator on a common block foundation, 1,050 t static (REQ-001 section 9)
Ventilation	enclosure ventilation air from the hall; hall ventilation for 1.2 MW enclosure heat (EPC).

LEGEND

- IEC supply (equipment outline)
- EPC item, shown as IEC space requirement
- maintenance / withdrawal space (keep free)
- laydown area
- crane hook coverage / crane
- crane pad / pre-assembly area (temporary)
- vehicle / heavy-haul access (SPMT)
- dimension (m)

VENDOR	Imaginary Electric Company - Power Generation Division (fictional)
PROJECT	Alpilla 600 MW CCGT - 1 x IE-9H.02 multi-shaft power island
CLIENT	Istanbul EPC (consortium leader) - EPC engineering
TITLE	GAS TURBINE AND GENERATOR - GA, MAINTENANCE AND INSTALLATION
DWG NO / REV	IEC-ALP-GA-101 Rev 0
SCALE / SHEET	1:300 on A1 / 1 of 1
COORDINATES	plant grid m; levels EL m (grade EL +15.0)
DATE / STATUS	2026-09-28 issued for EPC layout (reference)
NOTE	CASE STUDY - fictional; IEC proprietary